Enviroserve Wastewater Management Ltd

Kaiwaka
Northland
Ph 09 431 2434 Mobile 021 1300 821 **office@enviroserve.org.nz**

Date: 8 June 2020
Quote Number: ENVEXPL6-20
Property Address: Otehei Bay, Bay of Islands

To;
Supply and Install a 25,000 Ltr Primary Septic tank, connect to existing wastewater system.
Remove existing Grease Trap and fit 6000 Ltr Grease Trap @ Kitchen.
Rebuild Control Panel, install new circuits for Re-circulation Pump and new Irrigation Pump.
Decommission existing unused tanks.
Fit new recirculation pump, repurpose existing 4000 Ltr Primary as Irrigation tank.
Supply and Install new High Head Irrigation Pump to pump treated waste to new dispersal field.
Fit new main pipe from treatment system to top of hill to South.
Lay 3000 m2 dispersal field in three sectors with Sequencing Valve.

	$70354.90
GST	$ 10553.24
Total	$80,908.14

Optional extra; Supply and install new Remotely monitored GSM Fault alarm system. $1800.00 + GST.

Monitoring alarm Monthly $110.00 + GST.

Please note this does not include Ferry costs to and from Island.
All decommissioned tanks to remain on the Island.
Existing tanks must be emptied before work commences at Explore NZ cost.
This quote is based on Ferry returning Hiab truck on same day and ferry returning 13 Tonne Digger and 4 Wheel Truck following day.
Explore NZ must provide secure parking for 4 Wheel Truck in Opua area, otherwise this cost will be extra to quote.

Terms: 50% deposit prior to commencement. Balance 7 days on Invoice. Material and hireage prices on this quote subject to change without notice. Where actual conditions vary from supplied plans and documentation, additional costs may be incurred by client. The presence of rock, concrete rubble, high water tables or hazardous waste in excavation area may also incur additional costs. Unless expressly stated all services pipes ducts etc are to be located and marked by the Client signed above. Enviroserve accepts no liability for damage to or disruption of these services. Invoices not paid by due date incur interest at a rate of 2.5% per month or part thereof. Collection costs incurred for late payment of invoices are liable to be paid by Client signed above.

P H Warren
Registered Electrical Technician
Registered Certifying Drainlayer
Enviroserve Wastewater Management Ltd

Quote Acceptance

Please sign, detach and return this portion if you wish to accept the above quote.

I ..... (Client name) accept the above quote ENVEXPL6-20 price of ..... for the work detailed therein and agree to the standard terms and conditions below.

Date ..... Signed ..... (Client Signature)